INCH-POUND

MIL-DTL-29183/8B 13 March 2003 SUPERSEDING MIL-P-29183/8A 24 May 1985

DETAIL SPECIFICATION SHEET

PANELBOARD, POWER DISTRIBUTION, PORTABLE, WEATHERPROOF, TYPE I, CLASS 1, CONFIGURATION 6: 480 OR 208 VOLT, 240 KILOWATT, TERMINAL TYPE CONNECTORS

Inactive for new design after 13 March 2003

This specification is approved for use by all departments and agencies of the Department of Defense.

The requirements for acquiring the product described herein shall consist of this specification sheet and the issue of MIL-DTL-29183 listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation.

REQUIREMENTS: The distribution panel shall be as specified herein and in accordance with tables I and II, and figure 1.

Physical:

Weight: The weight shall not exceed 525 pounds (238 kilograms).

Dimensions (maximum):

Length: 70.5 inches (1791 millimeters (mm))

Width: 32.5 inches (826 mm) Height: 32.5 inches (826 mm)

Stability: The vertical center of gravity shall be not more than 21.0 inches (533 mm)

above level ground. Additional stability requirements shall apply in

accordance with MIL-DTL-29183.

AMSC N/A 1 of 4 FSC 6110

Electrical:

Input: The input to the distribution panel shall be 480 volt (V) or 208 V, 3-phase (Ø), 4-pole (P), 5-wire (W), 60 Hertz (Hz).

Bus capacity: The bus bar capacities shall be 800 amperes (A) (see figure 1).

Circuit breaker: The number of poles and current rating shall be as indicated in table I

herein and the voltage rating shall be sufficient for the intended

circuit.

PIN: The government part identification number (PIN) is as follows:





TABLE I. Circuit characteristics.

Quantity	Circuit kind	Circuit breaker Pole (P) - Ampere (A)	Interface connector
4	480V or 208V, 3-phase, 4P, 5W	3P-325A (without trip)	Terminals
4	480V or 208V, 3-phase, 4P, 5W	3P-325A	Terminals
2	480V or 208V, 3-phase, 4P, 5W	3P-100A	Terminals
2	480V or 208V, 3-phase, 4P, 5W	3P-50A	Terminals



NOTE:

* CIRCUIT BREAKERS 1, 2, 3, 4 SHALL NOT HAVE TRIP UNITS. THEY SHALL BE USED AS DISCONNECT DEVICES.

FIGURE 1. Single-line wiring diagram.

TABLE II. Connector assignment and connector terminal wiring.

Circuit	Function	Interface connector	Phase A, black wire	Phase B, red wire	Phase C, blue wire	Neutral, white wire	Ground, green (bare) wire
1, 2 3, 4	Input	Pressure type, terminal block, 250 kcmil ¹ wire size capacity	T1	T2	Т3	Т0	G
5, 6, 7, 8	Branch, 3-phase	Pressure type, terminal block, 250 kcmil ¹ wire size capacity	X	Y	Z	N	G
9, 10 11, 12	Branch, 3-phase	Pressure type, terminal block, minimum No. 1 AWG2 ² wire size capacity	X	Y	Z	N	G

¹ 1000 (k) circular (c) mils (mil). ² American wire gauge.

Custodian: Navy - YD Preparing Activity: DLA - GS2

(Project 6110-0443-008)

Review Activity: Navy - MC

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

- 1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
- 2. The submitter of this form must complete blocks 4, 5, 6, and 7.
- 3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

to amend contractual requirements.		,	,				
I RECOMMEND A CHANGE:	1. DOCUMENT NUMBE MIL-DTL-29183/8B	2. DOCU 200303	MENT DATE (YYYYMMDD) 813				
3. DOCUMENT TITLE PANELBOARD, POWER DISTRIBUTION, PORTABLE, WEATHERPROOF, TYPE I, CLASS 1, CONFIGURATION 6: 480 OR 208 VOLT, 240 KILOWATT, TERMINAL TYPE CONNECTORS							
4. NATURE OF CHANGE (Identify paragraph number	er and include proposed re	ewrite, if possible. Attach extra sheet	s as needed.)				
5. REASON FOR RECOMMENDATION							
6. SUBMITTER							
a. NAME (Last, First, Middle Initial)		b. ORGANIZATION					
c. ADDRESS (Include Zip Code)		d. TELEPHONE (Include Area Code) (1) Commercial (2) DSN (if applicable)	7. DATE SUBMITTED (YYYYMMDD)				
8. PREPARING ACTIVITY							
		b. TELEPHONE (Include Area Code)					
a. NAME Defense Supply Center Richmond		Commercial: (804) 279-5019 DSN: 695-5019					
c. ADDRESS (Include Zip Code)		IF YOU DO NOT RECEIVE A REPLY	WITHIN 45 DAYS, CONTACT:				
ATTN: DSCR-VBD (C. Hammond)		DEFENSE STANDARDIZATION PROGRAM OFFICE (DLSC-LM)					
8000 Jefferson Davis Highway Richmond, VA 23297-5610	1	8725 John J. Kingman Road, Suite 2533 Fort Belvoir, VA 22060-6221 Commercial: (703) 767-6888 DSN: 427-6888					
DD F 4400 FED 4000 (FO)			14/110/DIOD FED 00				